BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT53023

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/13/2022-23, Date: 23-08-2022

Name of Work:Works related to damaged caused due to Flood in ward No. 10 (Doddabommasandra).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Girish	
				In Figures	In Words
1	1069.74	Removing and Resetting of Footpath Slab etc complete as per specifications and directions of engineer in charge of the work	Sqm	224.66	Rupees Two Hundred Twenty Four and Sixty Six Paise Only
2	574.16	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost etc complete as per specifications and directions of engineer in charge of the work	Cum	195.6	Rupees One Hundred Ninety Five and Sixty Paise Only
3	20.1	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:4:8(M5) Using 40 mm nominal size graded crushed coarse aggregates etc complete as per specifications and directions of engineer in charge of the work	Cum	5474.63	Rupees Five Thousand Four Hundred Seventy Four and Sixty Three Paise Only
4	79.95	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates etc complete as per specifications and directions of engineer in charge of the work	Cum	6589.75	Rupees Six Thousand Five Hundred Eighty Nine and Seventy Five Paise Only
5	3.92	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications etc complete as per specifications and directions of engineer in charge of the work	Tonne	96926.0	Rupees Ninety Six Thousand Nine Hundred Twenty Six Only
6	503.46	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge of the Work.	Sqm	2234.2	Rupees Two Thousand Two Hundred Thirty Four and Twenty Paise Only
7	72	Providing & fixing RCC Precast Cover slab of 230mm thick for drain in cement concrete M20 using graded granite jelly 200mm & down size with steel reinforcement including formwork, lift charges, curing & concrete finished surface both sides etc,. And as per drawing & the direction of Engineer-in-charge	Sqm	5179.6	Rupees Five Thousand One Hundred Seventy Nine and Sixty Paise Only
8	539.71	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum etc complete as per specifications and directions of engineer in charge of the work	Cum	77.82	Rupees Seventy Seven and Eighty Two Paise Only
9	6770.03	Cost of Haulage Excluding Loading and Unloading, Case-1 : Surfaced Road A Taking output 10 t load and lead 10 km = 100 t.km etc complete as per specifications and directions of engineer in charge of the work	Kms	11.5	Rupees Eleven and Fifty Paise Only
10	2190	Providing and Fixing Steel Work in built up tubular (round rectangular hollowtube etc) truseses etc, including cutting, hoisting, fixing in postion and applying priming coat of approved steel primer including welding and bolted with Special shaped washer set complete electric resistance ordiction butt weleded tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of Engineer in Charge	Kgs	115.7	Rupees One Hundred Fifteen and Seventy Paise Only

Signature of the Contractor

Executive Engineer
Byaravanapura Division
BBMP, Bangalore - 92